



# TOWN OF ST. JOHNSBURY

Town Manager's Office  
51 Depot Square, Suite 3  
St. Johnsbury, VT 05819  
802-748-3926  
[www.stjvt.com](http://www.stjvt.com)

Town Clerk 802-748-4331  
Dispatch 802-748-2170  
Police 802-748-2170  
Fire 802-748-8925  
Public Works 802-748-4408

The Town of St. Johnsbury is planning to apply to the Vermont Community Development Program (VCDP) for a Community Development Block Grant (CDBG) in April of 2021.

Community Development Block Grant (CDBG) funding comes from the Federal Department of Housing and Urban Development (HUD). Section 106 of the National Historic Preservation Act of 1966 (NHPA) requires that federal agencies such as HUD consider the effect of their projects on any historic property, including historic buildings and archaeological sites.

The St. Johnsbury Armory Redevelopment Project will be broken into two phases. Phase 1, will be for site planning, remediations, and preparations for redevelopment. Phase 2, will consist of final design and construction. If awarded, VCDP funds will be used for Phase 1, and are contingent on Phase 2 completion.

## **Background:**

St. Johnsbury, the largest Town in the NEK, was first settled in 1786 and designated the Caledonia County seat in 1856. St. Johnsbury became a rail and highway junction as well as the industrial, commercial, and cultural crossroads of the NEK because of its proximity to the Passumpsic, Moose and Sleepers Rivers, as well as its proximity to Canada. Over the years, prosperity waned as roads replaced rivers as the primary form of transportation, and changes to the manufacturing industry forced many local businesses to close their doors. Thus, the Town has been littered with run-down abandoned former industrial and commercial properties (brownfields) for decades.

In 2019, the Vermont Department of Environmental Conservation (VTDEC) received a \$20,000 Small Technical Assistance Grant from the Environmental Protection Agency (EPA) for planning activities related to brownfield redevelopment in the town of St. Johnsbury. This planning grant provided an avenue for all of the necessary partners to come together to work through site challenges and identify a path forward to redevelop St. Johnsbury's Main Street corridor

The planning work conducted with this grant included a financial evaluation of different redevelopment strategies; the Armory property was prioritized because it had been vacant for the last decade and provided a significant opportunity for the Town as a driver of redevelopment on Main Street.

St. Johnsbury is on the cusp of turning its economy around. The Town has an opportunity to enhance its economy by focusing on creating a vibrant downtown, new business growth, attractive housing and neighborhoods, and leveraging its proximity to world class recreational facilities. We believe cleanup and revitalization of the Armory will not only protect the health of the many nearby

residents but will be the cornerstone project that will serve as a catalyst for economic development, improve public safety operations, and enhance livability in our community.

**Project Description:**

The Town of St. Johnsbury is interested in redeveloping the former Armory building located at 1249 Main Street for use as a municipal police station and regional emergency dispatch center. Owned by the Town, this building is within the historic district and represents a significant opportunity for the Town to drive economic redevelopment in this important downtown corridor. The building is contaminated and structurally compromised, which has caused developers to deem the project unfeasible in the past. The vacant building has no utility until properly remediated. The Town has continued to fund the basic maintenance, but there will soon be a need for capital investment just to prevent complete collapse of the structure.

The Select Board is committed to remediating the property and playing an active role in the property's redevelopment as a revitalization catalyst in this area.

- Lot Size: 0.44 acres (see attached existing conditions site plan prepared by Dufresne Group).
- Current Building Size: Approximately 16,100 sf. The building consists of an east wing and west wing. The east wing fronts on Main Street and is 3 stories including the usable basement. The west wing is 2 - 3 stories (including the basement) and contains a former gymnasium.
- Proposed Building Size: Approximately 11,300 sf. A portion of the west "gymnasium" wing will be removed and replaced with on-site parking and a carport
- The entire 3-story east wing fronting on Main Street will be preserved along with the 3-story section of the rear west wing.

(See attached Site Plan and Elevations)

**Project Cost:**

Preliminary cost estimating indicates a total project cost ranging from \$4.7 to \$5.2 million. A significant portion of this cost is for environmental remediation. As do similar buildings its age, the Armory contains abundant asbestos-containing materials, polychlorinated biphenyls (PCBs), and lead-based paint. Abatement costs associated with these materials are a major hurdle to future renovations. Environmental surveys previously completed at the site have identified and generally quantified the contamination in the building along with an opinion of probable cost for abatement. In June 2020, the Town procured a contractor to complete a remediation planning cost estimate for abatement at the Armory. The projected abatement costs range from \$800,000 to \$1.35 million. The Town of St. Johnsbury applied for EPA Clean-up funds in October of 2020 and expects to be notified about the funding request for \$500,000 in the spring of 2021. If awarded VCDP funds would be combined with EPA Clean-up funds and town funds to complete the Phase I brownfield remediation and preparations for redevelopment.

Phase II will include of the redevelopment into a police and dispatch center is estimated at \$3.9M.

(See attached remediation and construction cost estimates)

**Project Timeline:**


<b>Task</b>	<b>Target Date</b>
Launch Due Diligence/Preliminary Design	January 2021
Detailed Site Planning - Base Building Design Complete	July 2021
Local Permitting Complete	October 2021
Bond Vote	November 2021
Corrective Action Plan Approval	January 2022
State Permits Complete	January 2022
Bidding - Env. Remediation	February - April 2022
Final Architectural Design Complete	March 2022
Bidding - Building/Site Construction	April - July 2022
Environmental Remediation	July - December 2022
Building/Site Construction	December 2022 - August 2023
Occupy Building	September 2023




1 SITE PLAN  
P1 3/32" = 1'-0"

# PUBLIC SAFETY FACILITY

1249 MAIN STREET



2 3D - PARKING 1  
P1



3 3D - PARKING 2  
P1



**ARCHITECTS**  
25 Hercules Drive  
uite Two  
olchester, VT 05446  
02.655.5020  
02.622.6567  
[iemannlamphere.com](http://iemannlamphere.com)

# PUBLIC SAFETY FACILITY

# PUBLIC SAFETY FACILI

REVISION:	
DATE: 1/26/2021 4:26:37 PM	
SCALE:  PROJECT NO:	1/8" = 1'-0"
	2017067
CHECKED BY:  PPR	

CE DEPT.  
RMORY  
OVATION  
PLANS


# POLICE DEPT. ARMORY RENOVATION PLANS

A1 01

A1 01


WATSON

---




**1 FLOOR PLAN - BASEMENT**

BUILDING CODE AREA: 3,763  
BUILDING FOOT PRINT: 4,175



# **2 FLOOR PLAN - FIRST FLOOR**

BUILDING CODE AREA: 3,777 sf  
BUILDING FOOT PRINT: 4,060sf



# **3 FLOOR PLAN - SECOND FLOOR**

BUILDING CODE AREA: 3,770 sf  
BUILDING FOOT PRINT: 4,060 sf

Wiemann  
Lamphere

525 Hercules Drive  
Suite Two  
Colchester, VT 05446  
802.655.5020  
802.622.6567  
wiemannlamphere.com

## PUBLIC SAFETY FACILITY

VERMONT

ST. JOHNSBURY

NO. DATE: REVISION:


PROGRESS PRINT DATE:  
1/26/2021 4:26:42 PMSCALE:  
3/16" = 1'-0"PROJECT NO:  
2017067DRAWN BY:  
AuthorCHECKED BY:  
CheckerSHEET TITLE:  
ELEVATIONS

SHEET NUMBER:

A2.01



1 EAST  
A2.01 3/16" = 1'-0"



3 NORTH  
A2.01 3/16" = 1'-0"

Wiemann  
Lamphere

525 Hercules Drive  
Suite Two  
Colchester, VT 05446  
802.655.5020  
802.622.6567  
wiemannlamphere.com


## PUBLIC SAFETY FACILITY

VERMONT

ST. JOHNSBURY



1 SOUTH  
A2.02 3/16" = 1'-0"



2 WEST  
A2.02 3/16" = 1'-0"

NO.	DATE:	REVISION:

PROGRESS PRINT DATE:  
1/26/2021 4:26:47 PM

SCALE:  
3/16" = 1'-0"

PROJECT NO:  
2017067

DRAWN BY:  
Author

CHECKED BY:  
Checker

SHEET TITLE:

ELEVATIONS

SHEET NUMBER:


A2.02

Wiemann  
Lamphere



525 Hercules Drive  
Suite Two  
Colchester, VT 05446  
802.655.5020  
802.622.6567  
wiemannlamphere.com



MAIN STREET - LOOKING NW



MAIN STREET - LOOKING SW

2 3D VIEW  
A2.031 EAST - EXISTING MATERIALS  
A2.03 1/4" = 1'-0"

## PUBLIC SAFETY FACILITY

VERMONT

ST. JOHNSBURY

NO.	DATE:	REVISION:

PROGRESS PRINT DATE:	1/26/2021 4:26:50 PM
SCALE:	1/4" = 1'-0"
PROJECT NO:	2017067

DRAWN BY:	Author
CHECKED BY:	Checker

SHEET TITLE: EXISTING MATERIALS &amp; VIEWS

SHEET NUMBER: A2.03

A2.03

DEMOLITION KEY SCHEDULE	
KEY	DESCRIPTION
2A	DEMO EXTERIOR BRICK MASONRY WALL
2B	DEMO INTERIOR WALL PARTITION. PATCH AND REPAIR FLOOR AND CEILING FOR NEW CONSTRUCTION.
2C	DEMO SITE WALL TO EXTENT SHOWN ON PLAN
3A	DEMO EXTERIOR DOOR AND FRAME
3B	DEMO EXTERIOR WINDOW AND FRAME
3C	DEMO INTERIOR DOOR AND FRAME
3D	DEMO EXTERIOR WINDOW AND PREP FOR WINDOW REPLACEMENT
4A	REMOVE EXTERIOR CONCRETE STAIR
4B	REMOVE MILLWORK COUNTER
5A	REMOVE SINK, CAP PLUMBING IN WALL, COVER WITH S.S. PLATE
5B	REMOVE WALL HUNG URINAL, CAP PLUMBING BEHIND WALL, CAP WITH S.S. PLATE
5C	REMOVE FLOOR MOUNT TOILET

## DEMOLITION KEY SCHEDULE


## DESCRIPTION

2A	DEMO EXTERIOR BRICK MASONRY WALL
2B	DEMO INTERIOR WALL PARTITION. PATCH AND REPAIR FLOOR AND CEILING FOR NEW CONSTRUCTION.
2C	DEMO SITE WALL TO EXTENT SHOWN ON PLAN

3A	DEMO EXTERIOR DOOR AND FRAME
3B	DEMO EXTERIOR WINDOW AND FRAME
3C	DEMO INTERIOR DOOR AND FRAME
3D	DEMO EXTERIOR WINDOW AND PREP FOR WINDOW REPLACEMENT

4A	REMOVE EXTERIOR CONCRETE STAIR
4B	REMOVE MILLWORK COUNTER


5A	REMOVE SINK, CAP PLUMBING IN WALL, COVER WITH S.S. PLATE
5B	REMOVE WALL HUNG URINAL, CAP PLUMBING BEHIND WALL, CAP WITH S.S. PLATE
5C	REMOVE FLOOR MOUNT TOILET



## **2 DEMOLITION PLAN - LEVEL 1**

D1.01 1/8"


10 of 10



## 3 FLOOR PLAN - SECOND FLOOR

D1.01 1/8" = 1'-0"

Figure 1. A schematic diagram of the experimental setup. The laser beam passes through a lens and a polarizer, and is focused onto the sample surface by a lens. The scattered light is collected by a lens and detected by a photomultiplier tube.



## 1 FLOOR PLAN - BASEMENT

D1.01 1/8"

• 100 •

- 3 -

PUBLIC 3F

# POLICE DEPT. ARMORY DEMOLITION PLAN

D1 01



51 Knight Lane · PO Box 1486  
Williston, VT 05495  
Telephone 802-862-1980  
[www.atcgroupservices.com](http://www.atcgroupservices.com)

June 4, 2020

Mr. Joe Kasperzak  
Assistant Town Manager  
Town of St. Johnsbury  
51 Depot Square, Suite 3  
St. Johnsbury, VT 05819

Transmitted via electronic mail to: [jkasprzak@stjvt.com](mailto:jkasprzak@stjvt.com)

RE: 2020 Remediation Planning Cost Estimate  
St. Johnsbury Armory Building  
St. Johnsbury, Vermont  
ATC Project # 280BS01932

Dear Joe:

The following planning cost estimates are for PCB, Lead and Asbestos remediation and associated consulting costs associated with the St. Johnsbury Armory facility in St. Johnsbury, Vermont. The cost estimates are based on previous site investigation work conducted by ATC Group Services (ATC) at the facility to identify PCB, asbestos and lead containing materials at the site. ATC was contracted by the town of St. Johnsbury Vermont to provide this cost estimate for budget planning proposes.

#### **Background**

This cost estimate is based on the complete removal of all PCB Bulk Product and remediation waste, asbestos containing materials and lead based paint from the facility. Please note the provided estimates are based on ATC's experience and comparison to similar projects ATC has been involved with and are based on expected remediation costs only and do not include general construction, reconstruction or other associated project costs. Variables such as time of year, final scope, changes in disposal options and changes in regulation can have dramatic effect on the actual costs of the project. The cost estimates are based on 2020 rates and should be used for planning purposes only. Actual project costs may differ from planning cost estimates.

Future cost changes are hard to predict based on the numerous variables described above. However, for planning purposes it is ATC's experience that **labor and trucking rates** can be expected to increase at rate of approximately **1 to 2% per year**. Changes in disposal rates are more difficult to predict as waste facility designations and capacities change with time. It has been ATC's experience that **disposal rates** have not changed dramatically in the last 2 or 3 years. However, as facilities reach capacity other new or existing facilities could move in to fill the void. ATC would expect an increase in disposal costs of **2-3% annually**. Overall ATC would recommend the client to estimate a **2 to 3% annual increase** in project costs for future estimating purposes.



### PCB Containing Material Remediation Cost Estimate:

Previous testing has shown that PCB bulk product (>50 mg/Kg), PCB Remediation Waste (material impacted by bulk product >1 mg/kg and <50 mg/kg), and likely Excluded PCB products (<50 mg/kw, not impacted by a Bulk Product Waste and installed after 1980) are present at the site. The PCB Bulk Product wastes must be removed from the site, however, EPA does not give a mandated timeline for this to happen. Remediation wastes are required to be managed either by removal (option 1) or managed in place via an EPA approved plan (option 2). PCB containing materials classified as Excluded product do not have to be remediated from a regulatory standpoint but will need to be properly delineated and defined as Excluded Waste.

It is not anticipated at this time that the waste stream will be considered hazardous for lead (TCLP sample found to be in excess of 5ppm of lead) as well as PCB containing waste. While this is not the only variable that could affect costs associated with the remediation it does have the potential to be significant. Costs for disposal for non-lead hazardous PCB materials was assumed to be at an RCRA/EPA approved facility in Michigan. If the waste stream is determined to be hazardous for lead the disposal facility included for the estimate is an approved facility in Nevada. These facilities could change with time and as such will change the associated trucking and disposal costs.

ATC has included cost estimates for all the PCB Bulk Product, Remediation waste (both options) and excluded wastes. Please note all options include a 25% contingency.

Estimated costs for **Option 1**: estimates include the full removal of all PCB Bulk Product and Remediation Waste:

Non-Lead hazardous waste stream = \$267,900.00

Lead Hazardous waste stream = \$476,025.00

Estimated costs for **Option 2**: include the full removal of all PCB Bulk Product Waste (required), the in place management of Remediation Waste via an EPA approved plan, and the anticipated costs to develop that plan. Does not include costs associated with deed restrictions and annual monitoring likely required by EPA.

Non-Lead hazardous waste stream = \$625,375.00

Lead Hazardous waste stream = \$695,062.50

Excluded PCB product remediation costs: include the removal of all PCB containing materials. Estimates are based on disposal in the facilities listed above, however, these may be able to be disposed of at a facility in New England and therefore significantly less expensive.

Window caulking: Non-Lead hazardous waste stream = \$121,443.75

Lead Hazardous waste stream = \$170,656.25

Interior wall paint: Non-Lead hazardous waste stream = \$96,718.75

Lead Hazardous waste stream = \$156,875.00



### Asbestos Abatement Cost Estimate:

This cost estimate is for the asbestos abatement at the above referenced facility. This estimate is based on the complete removal of all identified thermal pipe insulation, plaster, Safe Door, Boiler, Window Caulking, Vibration Cloth, and fire brick throughout the facility. ATC assumes that the abatement contractors are given sufficient time periods to conduct the work and that significant overtime will not be required.

The planning budget includes an estimate for the asbestos abatement consulting costs including: abatement design, consulting and air monitoring. Consulting costs assumes six (6) site visits which includes six (6) PCM clearances for the project.

Estimated Asbestos Abatement Contractor Cost	\$316,400.00
Estimated Asbestos Abatement Consultant Costs	\$9,000.00

### Lead Abatement Costs

While significant Lead Based Painted (LBP) surfaces have been identified at the site, ATC does not anticipate any lead abatement to be required at the facility. The State of Vermont considers the abatement of lead based paint to be the permanent removal of a lead hazard from a facility. If LBP surfaces are impacted with the purpose of removing a lead hazard than that is considered abatement. If those same surfaces are impacted as a function of another activity, i.e. renovation, than the work is considered renovation and subject to the VOSHA lead in construction regulations.

Due to this fact, ATC believes that any LBP impacted at the site will be part of the renovation process and therefore not abatement but part of the selected general contractors VOSHA compliance.

ATC recommends that inclusion of a **\$10,000.00** contingency for VOSHA compliance for budgeting purposes.

Thank you for selecting ATC for your environmental management needs. If you have any questions feel free to contact us at 862-1980.

Sincerely,  
ATC

Jesse Stratton  
Project Manager  
Direct Line +1 802 871 8355  
Email: [jesse.stratton@atcgs.com](mailto:jesse.stratton@atcgs.com)

Thomas J Broido  
Branch Manager  
Direct Line +1 802 871 8346  
Email: [tom.broido@atcgs.com](mailto:tom.broido@atcgs.com)

# Saint Johnsbury Armory Redevelopment Project-DRAFT

## PHASE I: Environmental Review & Remediation

Hazardous Materials Remediation		\$1,163,855
Hazardous materials consultant		\$9,270
Environmental Review		\$50,000
General Admin. - Phase I Environmental Review & Remediation (in-kind)		\$36,406.99
<b>Total Phase I</b>		<b>1,259,532</b>

## PHASE II: Construction

Preliminary Estimate	PD Concept (Armory)
PD	Armory
<b>Subtotal CONSTRUCTION COSTS</b>	<b>\$2,778,561</b>
01	CM General Conditions Insurances
	\$203,733
	\$27,143
	\$84,771
	CM Fee
	\$216,595
	CM P&P Bond
	\$27,143
	Estimating Contingency
	\$311,421
<b>Subtotal CM COSTS</b>	<b>\$870,806</b>
<b>Total PROJECT COSTS</b>	<b>\$3,649,367</b>
Site Acquisition	
A/E Fees	\$273,702
Owner's Contingency	\$182,468
Site Improvements	incl.
Furniture Fixtures and Equipment	\$36,494
Tel / Data wiring	\$18,247
Security / CCTV	\$9,123
Local Permit	\$60
Water / sewer impact fees	\$0
Act 250 Application (If required)	\$0
Erosion Control Application	\$200
Fire Safety Permit	\$32,114
Easement / Legal Expenses	\$20,000
Testing and Inspection (conc/soil/hazmat)	\$24,000
Utility tie-ins / connections	\$0

Kitchen Eq. / Appliances		\$0
Artwork		\$0
Signage		\$6,000
Renewable Energy (Photo-voltaics)		\$100,000
Annual Escalator (not required if 2021)		\$197,142
<b>Subtotal</b>		<b>\$899,551</b>
General Admin. - Phase II Construction(in-kind)		\$43,543.36
<b>Total Phase I- Environmental Review &amp; Remediation</b>		<b>\$1,259,532</b>
<b>Total Phase II- Construction</b>		<b>\$4,592,461</b>
<b>Total</b>		<b>\$5,851,993</b>

Application Number: 07110-IG-2020-St. Johnsbury-45				
Town of St. Johnsbury				
Project Budget and Other Resources				
Other Resources	Funding Source	Type	Amount	Status
Municipal Contribution (MUNI) - Environmental Consultant	State/Local	Cash	\$25,000	Committed
Municipal Contribution (MUNI) - Town Economic Dev. Reserves	State/Local	Cash	\$75,000	Committed
Municipal Contribution (MUNI) - Town Economic Dev. Reserves	State/Local	Cash	\$123,125	Pending
Municipal Contribution (MUNI) - Project management by town	State/Local	Cash-In-Kind	\$36,407	Committed
Other (Other) - EPA Brownfields Cleanup Grant	Federal	Grant	\$500,000	Pending
Activity	VCDP Amount	MUNI	Other	Total Activity Costs
Program Management	\$34,270	\$25,000		\$59,270
Brownfield Clean Up	\$465,730	\$198,125	\$500,000	\$1,163,855
General Administration	\$0	\$36,407		\$36,407
Total Costs	\$500,000	\$259,532	\$500,000	\$1,259,532
Percentage of Total	40%	21%	40%	
<b>Remediation Budget Details:</b>				
	March 2021 Estimates			
PCB Removal	\$367,729.31			
Window Caulking	\$131,831.96			
Interior Wall Paint	\$121,185.94			
Asbestos Abatement	\$244,419.00			
Lead Abatement:				
VOSHA Compliance Contingency	\$10,300.00			
Contingency	\$288,388.74			
<b>Total Remediation</b>	<b>\$1,163,855</b>			
Environmental Consultant	\$25,000			
Archeological Consultant (ARA)	\$20,000			
Architectural Historian	\$5,000			
Asbestos Abatement Consultant	\$9,270.00			
Lead Abatement Consultant				
Total Environmental Review Consultants	\$59,270			
<b>Total</b>	<b>\$1,223,125</b>			
Town General Admin.	\$36,407			
<b>Total</b>	<b>\$1,259,532</b>			

**Standard Estimate Report**  
**St Johnsbury - Police Station - Armory**

**St. Johnsbury - Police Station - Armory - Main Street - Update**  
**Construction Cost Estimate - Schematic Design - February 2021**  
**Wiemann Lamphere Architects, Colchester, VT, 802-655-5020**

<b>Project name</b>	St. Johnsbury - Police Station - Armory Main Street St. Johnsbury VT
<b>Notes</b>	<ul style="list-style-type: none"><li>-Updated estimate based upon drawings dated 06/01/2020.</li><li>-Estimate includes for the gym demolition.</li><li>-Estimate includes \$ 200,000 for the new parking lot work.</li><li>-Costs for hazardous material removal and testing is not included.</li><li>-See estimate for assumptions, exclusions, work by others and work by the owner.</li><li>-Updated estimate in February 2021.</li><li>-Exterior masonry restoration added by allowance.</li><li>-North basement entry concrete ramp and ramp stairs &amp; walkway added.</li></ul>

**Standard Estimate Report**  
*St Johnsbury - Police Station - Armory*

February 14, 2021

Group	Phase	Item	Description	Takeoff Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Total Cost/Unit	Total Amount
<b>2000.00</b>			<b>DEMOLITION</b>							
	<b>2010.00</b>		<b>Demolition - General</b>							
		54	Demo-Boom Lift-To 40' H	80.00 hr	-	800	-	1,280	26.00 /hr	2,080
			<b>Demolition - General</b>			<b>800</b>		<b>1,280</b>	<b>/SF</b>	<b>2,080</b>
	<b>2012.00</b>		<b>Demolition - Concrete</b>							
		22	Demo Conc-Sawcut-Floor Slab	366.00 if	275	128	-	336	2.02 /if	738
		24	Demo Conc-Sawcut-Walls	1,200.00 if	1,688	420	-	2,063	3.48 /if	4,170
		26	Demo Conc-By Hand-Slabs-To 4" Thick	1,769.00 sf	3,980	-	-	4,865	5.00 /sf	8,845
		38	Demo Conc-By Hand-Walls-To 12" Thick	117.00 sf	1,620	-	-	1,980	30.77 /sf	3,600
		80	Demo Conc-Move Outside	31.00 cy	2,093	-	-	465	82.50 /cy	2,558
			<b>Demolition - Concrete</b>		<b>9,655</b>	<b>548</b>		<b>9,708</b>	<b>/SF</b>	<b>19,911</b>
	<b>2014.00</b>		<b>Demolition - Masonry</b>							
		20	Demo Masonry-Sawcut-Brick	3,118.00 if	4,385	1,091	-	2,436	2.54 /if	7,912
		26	Demo Masonry-Brick-Walls	1,549.93 cf	12,681	-	-	2,818	10.00 /cf	15,499
			<b>Demolition - Masonry</b>		<b>17,066</b>	<b>1,091</b>		<b>5,254</b>	<b>/SF</b>	<b>23,411</b>
	<b>2018.00</b>		<b>Demolition - Carpentry</b>							
		20	Demo Carpentry-Joists-To 2 x 12	1,345.00 If	1,513	-	-	-	1.13 /If	1,513
		22	Demo Carpentry-Rafter-To 2 x 12	2,116.00 If	2,506	-	-	-	1.18 /If	2,506
		26	Demo Carpentry-Beam-To 6 x 12	667.00 If	5,003	-	-	-	7.50 /If	5,003
		36	Demo Carpentry-Decking	4,553.00 sf	6,830	-	-	-	1.50 /sf	6,830
			<b>Demolition - Carpentry</b>		<b>15,851</b>				<b>/SF</b>	<b>15,851</b>
	<b>2020.00</b>		<b>Demolition - Millwork</b>							
		20	Demo Millwork-Cabinet-Base	22.00 If	198	-	-	-	9.00 /If	198
		24	Demo Millwork-Cabinet-Top-Plam	22.00 If	99	-	-	-	4.50 /If	99
			<b>Demolition - Millwork</b>		<b>297</b>				<b>/SF</b>	<b>297</b>
	<b>2022.00</b>		<b>Demolition - Roofing &amp; Insulation</b>							
		22	Demo Roofing-Shingles-Asphalt	2,784.00 sf	1,790	-	-	-	0.64 /sf	1,790
			<b>Demolition - Roofing &amp; Insulation</b>		<b>1,790</b>				<b>/SF</b>	<b>1,790</b>
	<b>2026.00</b>		<b>Demolition - Doors &amp; Windows</b>							
		20	Demo Opening-Door-Frame-To 4070	25.00 ea	844	-	-	-	33.75 /ea	844
		24	Demo Opening-Door-To 4070	25.00 ea	844	-	-	-	33.75 /ea	844
		38	Demo Opening-Window-To 25 Sqft	59.00 ea	2,655	-	-	-	45.00 /ea	2,655
			<b>Demolition - Doors &amp; Windows</b>		<b>4,343</b>				<b>/SF</b>	<b>4,343</b>
	<b>2028.00</b>		<b>Demolition - Finishes</b>							
		30	Demo Finish-Floor-Resilient-Tile	792.00 sf	792	-	-	88	1.11 /sf	880
		38	Demo Finish-Floor-Wood	1,769.00 sf	2,654	-	-	-	1.50 /sf	2,654
		44	Demo Finish-Floor-Mastic	7,292.00 sf	2,188	-	-	365	0.35 /sf	2,552
		56	Demo Finish-Ceiling-Plaster-On Wd Lath	7,292.00 sf	10,938	-	-	-	1.50 /sf	10,938
		62	Demo Finish-Ceiling-ACT-Tile & Grid	7,292.00 sf	2,625	-	-	-	0.36 /sf	2,625
		96	Demo Finish-Walls-Stud x 2PLS	3,250.00 sf	4,179	-	-	-	1.29 /sf	4,179
			<b>Demolition - Finishes</b>		<b>23,375</b>			<b>453</b>	<b>/SF</b>	<b>23,827</b>
	<b>2040.00</b>		<b>Demolition - Specialty Items</b>							
		26	Demo Item-Partition-Toilet	1.00 ea	45	-	-	-	45.00 /ea	45
			<b>Demolition - Specialty Items</b>		<b>45</b>				<b>/SF</b>	<b>45</b>
	<b>2062.00</b>		<b>Demolition - Buildings &amp; Structures</b>							
		34	Demo Building-Masonry	128,700.00 cf	-	-	51,480	-	0.40 /cf	51,480
		40	Demo Building-Foundation	230.00 cy	-	-	34,500	-	150.00 /cy	34,500
		42	Demo Building-Dump Fee's	20.00 bx	-	15,000	-	-	750.00 /bx	15,000
			<b>Demolition - Buildings &amp; Structures</b>		<b>15,000</b>		<b>85,980</b>		<b>/SF</b>	<b>100,980</b>
	<b>2082.00</b>		<b>Demolition - Cut &amp; Patch</b>							
		32	Cut & Patch-Plumbing	42.00 If	2,520	420	-	462	81.00 /If	3,402
			<b>Demolition - Cut &amp; Patch</b>		<b>2,520</b>	<b>420</b>		<b>462</b>	<b>/SF</b>	<b>3,402</b>
	<b>2090.00</b>		<b>Demolition - Hazardous</b>							
		10	Hazardous-Abatement & Testing	0.00 ls	-	-	0	-	0.00 /ls	0
	<b>2094.00</b>		<b>Demolition - Cutting &amp; Coring</b>							
		20	Cut-Wood-To 1" Thick	936.00 If	2,808	-	-	234	3.25 /If	3,042
			<b>Demolition - Cutting &amp; Coring</b>		<b>2,808</b>			<b>234</b>	<b>/SF</b>	<b>3,042</b>
	<b>2096.00</b>		<b>Demolition - Debris &amp; Handling</b>							
		22	Debris-Dumpster-30 Cuyd C & D	270.00 cy	-	6,750	-	-	25.00 /cy	6,750
		72	Debris-Move Out	270.00 cy	7,898	-	-	-	29.25 /cy	7,898
			<b>Demolition - Debris &amp; Handling</b>		<b>7,898</b>	<b>6,750</b>	<b>85,980</b>	<b>17,390</b>	<b>/SF</b>	<b>14,648</b>
			<b>DEMOLITION</b>		<b>85,646</b>	<b>24,609</b>	<b>85,980</b>			<b>213,626</b>
<b>2100.00</b>			<b>SITE WORK</b>							
	<b>2110.00</b>		<b>Site Work - General</b>							
		10	Site Work-Estimate-By DeWolfe	1.00 ls	-	-	200,000	-	200,000.00 /ls	200,000
			<b>Site Work - General</b>				<b>200,000</b>		<b>/SF</b>	<b>200,000</b>
	<b>2112.00</b>		<b>Site Work - Demolition</b>							
		30	Site Demo-Concrete-North Walk Area	45.00 cy	-	-	-	7,000	155.56 /cy	7,000
		100	Site Demo-Debris-Load To Truck	45.00 cy	-	-	-	173	3.85 /cy	173
		102	Site Demo-Debris-Haul Off Site	45.00 cy	-	-	-	346	7.69 /cy	346
		106	Site Demo-Debris-Disposal-Concrete	45.00 cy	-	675	-	-	15.00 /cy	675
			<b>Site Work - Demolition</b>		<b>675</b>	<b>7,519</b>		<b>7,519</b>	<b>/SF</b>	<b>8,194</b>
	<b>2202.00</b>		<b>Site Work - Building</b>							
		*20	Building-Excavate-Trench	410.00 cy	633	-	-	2,463	7.55 /cy	3,096
		*26	Building-Backfill-Backhoe	243.00 cy	312	-	-	1,215	6.29 /cy	1,527
		*28	Building-Backfill-Compaction-Plate	243.00 cy	729	-	-	243	4.00 /cy	972
		*38	Building-Backfill-Import-Crush Gravel	243.00 cy	-	5,832	-	-	24.00 /cy	5,832

**Standard Estimate Report**  
*St Johnsbury - Police Station - Armory*

February 14, 2021

Group	Phase	Item	Description	Takeoff Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Total Cost/Unit	Total Amount
	2202.00		<b>Site Work - Building</b>							
		*70	Building-Slab Base-Fine Grade	2,536.00 sf	228	-	-	298	0.21 /sf	527
		72	Building-Slab Base-Crush Gravel	46.00 cy	41	1,104	-	253	30.40 /cy	1,398
		76	Building-Slab Base-Sand	21.00 cy	19	252	-	116	18.40 /cy	386
		82	Building-Fabric-Stabilization-Small Area	828.00 sf	149	79	-	55	0.34 /sf	284
		*92	Building-Waste Excess-Load & Haul-Away	410.00 cy	-	-	-	4,994	12.18 /cy	4,994
			<b>Site Work - Building</b>		<b>2,112</b>	<b>7,267</b>		<b>9,636</b>	<b>/SF</b>	<b>19,016</b>
	2204.00		<b>Site Work - Roads &amp; Walks</b>							
		30	Subbase-Spread & Compact-Pads & Walks	16.00 cy	72	-	-	200	17.00 /cy	272
		72	Subbase-Import-Crush Gravel	16.00 cy	-	384	-	-	24.00 /cy	384
		80	Subbase-Fine Grade-Pads & Walks	417.00 sf	75	-	-	83	0.38 /sf	158
			<b>Site Work - Roads &amp; Walks</b>		<b>147</b>	<b>384</b>		<b>283</b>	<b>/SF</b>	<b>814</b>
			<b>SITE WORK</b>		<b>2,259</b>	<b>8,326</b>	<b>200,000</b>	<b>17,439</b>	<b>/SF</b>	<b>228,025</b>
2400.00			<b>SITE IMPROVEMENTS</b>							
	2450.00		<b>Site - Landscaping</b>							
		10	Landscape-Estimate-By DeWolfe	1.00 ls	-	-	*	-	0.00 /ls	0
	2456.00		<b>Site - Lawns</b>							
		14	Lawn-Exist-Restore	2,000.00 sf	-	-	3,000	-	1.50 /sf	3,000
			<b>Site - Lawns</b>				<b>3,000</b>		<b>/SF</b>	<b>3,000</b>
			<b>SITE IMPROVEMENTS</b>				<b>3,000</b>		<b>/SF</b>	<b>3,000</b>
3000.00			<b>CONCRETE - BUILDING</b>							
	3052.00		<b>Concrete - Form Strip Footings</b>							
		10	Form Strip Footings-2 x 4 Keyway	61.00 lf	81	25	-	-	1.74 /lf	106
		14	Form Strip Footings-3 Use	122.00 sf	596	127	-	-	5.93 /sf	724
			<b>Concrete - Form Strip Footings</b>		<b>677</b>	<b>152</b>			<b>/SF</b>	<b>830</b>
	3054.00		<b>Concrete - Form Spread Footings</b>							
		*12	Form Spread Footings-3 Use	236.00 sf	1,335	234	-	-	6.65 /sf	1,569
			<b>Concrete - Form Spread Footings</b>		<b>1,335</b>	<b>234</b>			<b>/SF</b>	<b>1,569</b>
	3060.00		<b>Concrete - Form Walls</b>							
		30	Form Walls-Symons- 0' to 8' H	2,570.00 sf	10,794	2,968	-	-	5.36 /sf	13,762
			<b>Concrete - Form Walls</b>		<b>10,794</b>	<b>2,968</b>			<b>/SF</b>	<b>13,762</b>
	3064.00		<b>Concrete - Form Slabs On Grade</b>							
		16	Form Slabs-Edge Forms	32.00 sf	172	26	-	-	6.20 /sf	198
		26	Form Slabs-Vapor Barrier-15 Mil	1,708.00 sf	233	282	-	-	0.30 /sf	515
			<b>Concrete - Form Slabs On Grade</b>		<b>405</b>	<b>308</b>			<b>/SF</b>	<b>713</b>
	3066.00		<b>Concrete - Form Square Columns</b>							
		*12	Form Columns-Square-Plywood-3 Use	276.00 sf	2,697	380	-	-	11.15 /sf	3,077
			<b>Concrete - Form Square Columns</b>		<b>2,697</b>	<b>380</b>			<b>/SF</b>	<b>3,077</b>
	3080.00		<b>Concrete - Inserts &amp; Sleeves</b>							
		24	Inserts-Chamfer Strip- 3/4"	28.00 lf	34	6	-	-	1.42 /lf	40
		26	Inserts-Chamfer Strip- 1"	128.00 lf	154	56	-	-	1.64 /lf	210
			<b>Concrete - Inserts &amp; Sleeves</b>		<b>187</b>	<b>62</b>			<b>/SF</b>	<b>250</b>
	3082.00		<b>Concrete - Expansion Joints</b>							
		14	Expan Joints-Metal Keys- 5.50"	36.00 lf	120	52	-	-	4.77 /lf	172
		24	Expan Joints-Bituminous- 6.00"	64.00 lf	110	50	-	-	2.49 /lf	160
			<b>Concrete - Expansion Joints</b>		<b>230</b>	<b>102</b>			<b>/SF</b>	<b>331</b>
	3086.00		<b>Concrete - Control Joints &amp; Sawcuts</b>							
		10	Joints-Control-Sawcut-Green- 1.00" Deep	200.00 lf	114	11	-	27	0.76 /lf	152
			<b>Concrete - Control Joints &amp; Sawcuts</b>		<b>114</b>	<b>11</b>		<b>27</b>	<b>/SF</b>	<b>152</b>
	3088.00		<b>Concrete - Reinforcing Steel</b>							
		*28	Steel Rebar-Footings	2,321.79 lb	1,238	1,405	-	-	1.14 /lb	2,643
		32	Steel Rebar-Mats	4,458.03 lb	2,378	2,697	-	-	1.14 /lb	5,075
		*38	Steel Rebar-Columns	875.47 lb	981	530	-	-	1.73 /lb	1,510
		*40	Steel Rebar-Slab On Grade	2,212.42 lb	1,458	1,339	-	-	1.26 /lb	2,796
			<b>Concrete - Reinforcing Steel</b>		<b>6,054</b>	<b>5,970</b>			<b>/SF</b>	<b>12,024</b>
	3090.00		<b>Concrete - Welded Wire Mesh</b>							
		20	Wire Mesh- 6 x 6 x 10/10	5,246.00 sf	1,908	1,045	-	-	0.56 /sf	2,953
			<b>Concrete - Welded Wire Mesh</b>		<b>1,908</b>	<b>1,045</b>			<b>/SF</b>	<b>2,953</b>
	3092.00		<b>Concrete - Reinforcing Accessories</b>							
		*12	Reinforcing-Bolsters-Bricks	2,273.50 sf	500	102	-	-	0.27 /sf	602
		32	Reinforcing-Bolsters-Chairs-On Grade	828.00 sf	228	83	-	-	0.38 /sf	311
		52	Reinforcing-Bolsters-Chairs-On Deck	3,538.00 sf	973	354	-	-	0.38 /sf	1,327
			<b>Concrete - Reinforcing Accessories</b>		<b>1,701</b>	<b>539</b>			<b>/SF</b>	<b>2,240</b>
	3098.00		<b>Concrete - Place Strip Footings</b>							
		12	Place Strip Footings-Concrete-3000 PSI	7.91 cy	-	1,015	-	-	128.27 /cy	1,015
		24	Place Strip Footings-By Pump	7.91 cy	300	-	-	150	56.84 /cy	450
			<b>Concrete - Place Strip Footings</b>		<b>300</b>	<b>1,015</b>		<b>150</b>	<b>/SF</b>	<b>1,464</b>
	3100.00		<b>Concrete - Place Spread Footings</b>							
		12	Place Spread Footings-Concrete-3000 PSI	9.33 cy	-	1,197	-	-	128.26 /cy	1,197
		16	Place Spread Footings-Concrete-4000 PSI	3.70 cy	-	503	-	-	135.67 /cy	503
		22	Place Spread Footings-By Truck	3.70 cy	233	-	-	-	63.00 /cy	233
		24	Place Spread Footings-By Pump	9.33 cy	560	-	-	280	90.00 /cy	840
			<b>Concrete - Place Spread Footings</b>		<b>793</b>	<b>1,699</b>		<b>280</b>	<b>/SF</b>	<b>2,772</b>
	3106.00		<b>Concrete - Place Walls</b>							
		12	Place Walls-Concrete-3000 PSI	58.71 cy	-	7,530	-	-	128.26 /cy	7,530
		24	Place Walls-By Pump	58.71 cy	2,114	-	-	1,057	54.00 /cy	3,170

**Standard Estimate Report**  
**St Johnsbury - Police Station - Armory**

February 14, 2021

Group	Phase	Item	Description	Takeoff Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Total Cost/Unit	Total Amount
			Concrete - Place Walls			2,114	7,530			1,057
			Concrete - Place Slab On Grade						/SF	10,701
3110.00		12	Place Slab On Grade-Concrete-3000 PSI	28.99 cy	-	3,718	-	-	128.26 /cy	3,718
		16	Place Slab On Grade-Concrete-4000 PSI	15.33 cy	-	2,080	-	-	135.68 /cy	2,080
		22	Place Slab On Grade-By Truck	15.33 cy	460	-	-	-	30.00 /cy	460
		24	Place Slab On Grade-By Pump	28.99 cy	870	-	-	435	45.00 /cy	1,305
			Concrete - Place Slab On Grade			1,330	5,799			435
3112.00			Concrete - Place Columns							
		12	Place Columns-Concrete-3000 PSI	1.17 cy	-	150	-	-	128.24 /cy	150
		16	Place Columns-Concrete-4000 PSI	2.67 cy	-	362	-	-	135.68 /cy	362
		22	Place Columns-By Truck	2.67 cy	105	-	-	-	39.37 /cy	105
		24	Place Columns-By Pump	1.17 cy	47	-	-	23	60.00 /cy	70
			Concrete - Place Columns			152	512			23
3116.00			Concrete - Place Elevated Slabs							
		12	Place Elevated Slab-Concrete-3000 PSI	49.14 cy	-	6,303	-	-	128.26 /cy	6,303
		22	Place Elevated Slab-By Pump	49.14 cy	1,361	-	-	680	41.54 /cy	2,041
			Concrete - Place Elevated Slabs			1,361	6,303			680
3124.00			Concrete - Place & Finish Pan Stairs							
		12	Place Stair Fill-Concrete-3000 PSI	1.90 cy	-	244	-	-	128.26 /cy	244
		22	Place Stair Fill-By Hand	258.00 sf	774	-	-	-	3.00 /sf	774
			Concrete - Place & Finish Pan Stairs			774	244			
3128.00			Concrete - Floor Finishing							
		10	Floor Finish-Broom	828.00 sf	994	704	-	-	2.05 /sf	1,697
		12	Floor Finish-Steel Trowel-Walk Behind	5,246.00 sf	4,197	-	-	350	0.87 /sf	4,547
		*16	Floor Finish-Float	1,058.50 sf	977	-	-	16	0.94 /sf	993
			Concrete - Floor Finishing			6,167	704			366
3130.00			Concrete - Wall Finishing							
		10	Wall Finish-Break Ties & Patch	2,570.00 sf	2,827	141	-	-	1.16 /sf	2,968
			Concrete - Wall Finishing			2,827	141			
3131.00			Concrete - Beam & Column Finishing							
		14	Beam & Column-Float Grout	96.00 sf	211	53	-	-	2.75 /sf	264
			Concrete - Beam & Column Finishing			211	53			
3132.00			Concrete - Concrete Curing							
		*10	Concrete-Cure-Wet Burlap	2,536.00 sf	558	558	-	-	0.44 /sf	1,116
		*12	Concrete-Cure-Spray-1 Coat	7,565.00 sf	925	1,248	-	-	0.29 /sf	2,173
			Concrete - Concrete Curing			1,483	1,806			
		<b>CONCRETE - BUILDING</b>				43,613	37,576			3,018
3150.00			<b>CONCRETE - SITE</b>							
	3162.00		Concrete - Site - By Cuyd							
		24	Concrete-North Ramp-Footings-Strip	11.00 cy	2,310	1,694	-	55	369.00 /cy	4,059
		30	Concrete-North Ramp-Walls-High	30.00 cy	9,450	9,480	-	450	646.00 /cy	19,380
		36	Concrete-North Ramp-Stairs	4.00 cy	1,440	1,000	-	80	630.00 /cy	2,520
		38	Concrete-North Ramp-Walk- 5"	7.00 cy	1,470	1,750	-	175	485.00 /cy	3,395
			Concrete - Site - By Cuyd			14,670	13,924			760
			<b>CONCRETE - SITE</b>			14,670	13,924			760
4000.00			<b>MASONRY</b>							
	4210.00		Masonry - Brick							
		20	Brick-Veneer-Standard-Red	2,904.00 sf	53,724	15,391	7,260	3,630	27.55 /sf	80,005
			Masonry - Brick			53,724	15,391			3,630
	4230.00		Masonry - Concrete Unit							
		44	Concrete Block-Interior- 8"	2,560.26 sf	27,066	8,142	6,401	1,829	16.97 /sf	43,437
		50	Concrete Block-Bond Beam- 8" x 8"-Grout	213.00 lf	2,627	1,377	533	178	22.13 /lf	4,714
		54	Concrete Block-Lintel- 8" x 8"-Grout	43.00 lf	361	205	108	43	16.67 /lf	717
		66	Concrete Block-Grout Cores- 8"	497.97 sf	1,743	713	1,245	207	7.85 /sf	3,908
		72	Concrete Block-Grout-Frames-3070	10.00 ea	382	138	25	45	59.01 /ea	590
		80	Concrete Block-Rebar-#5 & #6-Horiz	444.32 lb	474	269	-	-	1.67 /lb	743
		120	Concrete Block-Rebar-#5 & #6-Vert	1,038.76 lb	1,385	628	-	-	1.94 /lb	2,013
			Masonry - Concrete Unit			34,037	11,472	8,311		2,302
	4600.00		Masonry - Staging & Scaffolding							
		16	Staging-Rental-Erect & Remove	2,560.26 sf	9,900	-	-	853	4.20 /sf	10,753
		18	Staging-Rental-Per SF Month	2,560.26 sfm	-	1,280	-	-	0.50 /sfm	1,280
		20	Staging-Rental-Planks-Per SF	2,560.26 sf	-	2,560	-	-	1.00 /sf	2,560
			Masonry - Staging & Scaffolding			9,900	3,840			853
4999.00			Masonry - Misc							
		34	Masonry-Insulation-Rigid- 2.00"	2,904.00 sf	2,697	3,630	-	207	2.25 /sf	6,534
			Masonry - Misc			2,697	3,630			207
			<b>MASONRY</b>			100,358	34,333	15,571		6,993
5000.00			<b>STEEL</b>							
	5010.00		Steel - General							
		10	Steel-Exist-Upgrade-Floors & Roof	0.00 ls	-	-	0	-	0.00 /ls	0
	5100.00		Structural Steel							
		28	Structural-10.0 Lb/Sqft-Car Port	1,000.00 sf	-	-	27,500	-	27.50 /sf	27,500
		30	Structural-12.0 Lb/Sqft	5,697.00 sf	-	-	153,819	-	27.00 /sf	153,819
		60	Structural-Floor Deck-1.50" x 20 Ga	3,798.00 sf	-	-	12,533	-	3.30 /sf	12,533
		*70	Structural-Roof Deck-1.50" x 20 Ga	2,899.00 sf	-	-	8,697	-	3.00 /sf	8,697

**Standard Estimate Report**  
*St Johnsbury - Police Station - Armory*

February 14, 2021

Group	Phase	Item	Description	Takeoff Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Total Cost/Unit	Total Amount
			<b>Structural Steel</b>				<b>202,549</b>		/SF	<b>202,549</b>
			<b>STEEL</b>				<b>202,549</b>		/SF	<b>202,549</b>
<b>5500.00</b>			<b>METAL FABRICATIONS</b>							
	<b>5510.00</b>		<b>Misc. Metals - Interior</b>							
		22 Metals- Stair-Pan Type-Guard Rail-48" W	41.00 rs	-	-	29,315	-	715.00 /rs		29,315
		28 Metals- Stair-Pan Type-Landings	93.00 sf	-	-	8,370	-	90.00 /sf		8,370
		50 Metals-Ladder-Vertical-Steel	14.00 vf	513	1,400	-	-	136.67 /vf		1,913
		54 Metals-Ladder-Vertical-Elevator	8.00 vf	293	600	-	-	111.67 /vf		893
		90 Metals-Grating-Sump-Elevator	1.00 ea	158	650	-	-	807.50 /ea		808
		134 Metals-Steel-Angle-Sills-Elevator	540.00 lb	551	891	-	324	3.27 /lb		1,766
		142 Metals-Steel-Angle-Lintels	350.00 lb	509	481	-	-	2.83 /lb		990
		160 Metals-Steel-Add-Galvanize	350.00 lb	-	212	-	-	0.61 /lb		212
		<b>Misc. Metals - Interior</b>		<b>2,024</b>	<b>4,234</b>	<b>37,685</b>	<b>324</b>	/SF		<b>44,267</b>
	<b>5520.00</b>		<b>Misc. Metals - Exterior</b>							
		34 Metals-Rail-Wall Mtd 1 Line-Steel-Galv	148.00 lf	3,053	5,920	-	-	60.63 /lf		8,973
		<b>Misc. Metals - Exterior</b>		<b>3,053</b>	<b>5,920</b>			/SF		<b>8,973</b>
<b>5800.00</b>			<b>Expansion Control</b>							
		20 Expansion-Joints-Ceiling-To 2.00"	61.00 lf	1,046	1,342	-	87	40.57 /lf		2,475
		22 Expansion-Joints-Floor-To 2.00"	122.00 lf	2,091	2,684	-	174	40.57 /lf		4,950
		24 Expansion-Joints-Wall-To 2.00"	98.00 lf	1,646	2,112	-	137	40.57 /lf		3,895
		26 Expansion-Joints-Wall-To 2.00"-Exterior	48.00 lf	823	1,848	-	69	57.07 /lf		2,739
		<b>Expansion Control</b>		<b>5,606</b>	<b>7,966</b>		<b>467</b>	/SF		<b>14,059</b>
		<b>METAL FABRICATIONS</b>		<b>10,682</b>	<b>18,140</b>	<b>37,685</b>	<b>791</b>	/SF		<b>67,298</b>
<b>6000.00</b>			<b>ROUGH CARPENTRY</b>							
	<b>6104.00</b>		<b>Blocking &amp; Strapping</b>							
		*22 Blocking-Int-To Steel-2 x 6-FT	758.00 lf	2,274	1,126	-	-	4.49 /lf		3,400
		122 Blocking-Ext-To Masonry-2 x 6-PT	816.00 lf	2,720	763	-	-	4.27 /lf		3,483
		152 Blocking-Ext-To Steel-2 x 6-PT	160.00 lf	480	150	-	-	3.94 /lf		630
		172 Blocking-Roof-To Steel-2 x 6-PT	280.00 lf	840	262	-	-	3.94 /lf		1,102
		344 Blocking-PWD-FT-3/4"-Backers	96.00 sf	288	180	-	-	4.87 /sf		468
		<b>Blocking &amp; Strapping</b>		<b>6,602</b>	<b>2,480</b>			/SF		<b>9,082</b>
	<b>6126.00</b>		<b>Wall Sheathing</b>							
		32 Wall Sheath-CDX-3/4"	213.00 sf	399	205	-	-	2.84 /sf		604
		<b>Wall Sheathing</b>		<b>399</b>	<b>205</b>			/SF		<b>604</b>
	<b>6190.00</b>		<b>Fasteners</b>							
		16 Fastener-Materials	1.00 ls	-	60	-	-	60.00 /ls		60
		20 Fastener-Rough Hardware	1.00 ls	-	30	-	-	30.00 /ls		30
		<b>Fasteners</b>			<b>90</b>			/SF		<b>90</b>
	<b>6199.00</b>		<b>Rough Carpentry - Misc</b>							
		112 R Carp-Matl Handling-Unload & Stock	1.00 ls	270	-	-	-	375	645.00 /ls	645
		<b>Rough Carpentry - Misc</b>		<b>270</b>			<b>375</b>	/SF		<b>645</b>
		<b>ROUGH CARPENTRY</b>		<b>7,271</b>	<b>2,775</b>		<b>375</b>	/SF		<b>10,421</b>
<b>6200.00</b>			<b>FINISH CARPENTRY</b>							
	<b>6224.00</b>		<b>Interior Trim - Boards &amp; Mouldings</b>							
		72 Int Trim-Board-Maple- 1 x 4	183.00 lf	1,487	439	-	-	-	10.53 /lf	1,926
		76 Int Trim-Board-Maple- 1 x 8	183.00 lf	1,983	988	-	-	-	16.23 /lf	2,971
		<b>Interior Trim - Boards &amp; Mouldings</b>		<b>3,469</b>	<b>1,427</b>			/SF		<b>4,897</b>
		<b>FINISH CARPENTRY</b>		<b>3,469</b>	<b>1,427</b>			/SF		<b>4,897</b>
<b>6400.00</b>			<b>ARCHITECTURAL MILLWORK</b>							
	<b>6410.00</b>		<b>Architectural Millwork - General</b>							
		22 Millwork-Shops & Delivery	1.00 ls	-	3,500	-	-	-	3,500.00 /ls	3,500
		30 Millwork-Unload & Stock	1.00 ls	360	-	-	-	-	360.00 /ls	360
		40 Millwork-Cabinet-WD-Base	25.00 lf	1,219	5,625	-	-	-	273.75 /lf	6,844
		42 Millwork-Cabinet-WD-Wall-Drs	25.00 lf	650	3,750	-	-	-	176.00 /lf	4,400
		62 Millwork-Cabinet-WD-Squad	52.00 lf	3,380	15,600	-	-	-	365.00 /lf	18,980
		62 Millwork-Cabinet-WD-Cubbies-Equip	15.00 lf	975	4,500	-	-	-	365.00 /lf	5,475
		64 Millwork-Cabinet-WD-Benches	29.00 lf	1,414	4,350	-	-	-	198.75 /lf	5,764
		<b>Architectural Millwork - General</b>		<b>7,998</b>	<b>37,325</b>			/SF		<b>45,323</b>
	<b>6420.00</b>		<b>Cabinetry &amp; Countertops</b>							
		38 Countertops-PLM-30"-Custom	25.00 lf	650	1,238	-	-	-	75.50 /lf	1,888
		<b>Cabinetry &amp; Countertops</b>		<b>650</b>	<b>1,238</b>			/SF		<b>1,888</b>
		<b>ARCHITECTURAL MILLWORK</b>		<b>8,648</b>	<b>38,563</b>			/SF		<b>47,210</b>
<b>7000.00</b>			<b>THERMAL &amp; MOISTURE</b>							
	<b>7012.00</b>		<b>Waterproofing</b>							
		56 Waterproofing-Vertical-Sheet-Bituthene	1,105.00 sf	1,216	1,671	-	-	-	2.61 /sf	2,887
		60 Waterproofing-Pits-Crystalline	200.00 sf	-	-	1,200	-	-	6.00 /sf	1,200
		<b>Waterproofing</b>		<b>1,216</b>	<b>1,671</b>	<b>1,200</b>		/SF		<b>4,087</b>
	<b>7020.00</b>		<b>Air &amp; Vapor Barriers</b>							
		16 AV Barriers-Building-Air Seal-To Code	5,176.00 sf	1,242	269	-	-	-	0.29 /sf	1,501
		62 AV Barriers-Spray On-Fluid	2,904.00 sf	-	-	10,164	-	-	3.50 /sf	10,164
		84 AV Barriers-Flashings-Membrane- 9"	300.00 lf	550	202	-	-	-	2.51 /lf	752
		92 AV Barriers-Flashings-Sills-12"	26.00 lf	72	75	-	-	-	5.63 /lf	146
		<b>Air &amp; Vapor Barriers</b>		<b>1,864</b>	<b>535</b>	<b>10,164</b>		/SF		<b>12,563</b>
	<b>7100.00</b>		<b>Fireproofing</b>							
		24 Fireproofing-Cementitious	5,697.00 sf	-	-	22,788	-	-	4.00 /sf	22,788

**Standard Estimate Report**  
St Johnsbury - Police Station - Armory

February 14, 2021

Group	Phase	Item	Description	Takeoff Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Total Cost/Unit	Total Amount
			<b>Fireproofing</b>				<b>22,788</b>		/SF	<b>22,788</b>
			<b>THERMAL &amp; MOISTURE</b>		<b>3,079</b>	<b>2,207</b>	<b>34,152</b>		/SF	<b>39,438</b>
<b>7200.00</b>			<b>INSULATION</b>							
	<b>7220.00</b>		<b>Insulation - Building - Rigid - Foundations</b>							
		34	Rigid-Vertl-25-Polystryrene- 2.00"	1,105.00 sf	1,085	1,405	-		2.25 /sf	2,491
			<b>Insulation - Building - Rigid - Foundations</b>		<b>1,085</b>	<b>1,405</b>			/SF	<b>2,491</b>
	<b>7224.00</b>		<b>Insulation - Building - Rigid - Slab On Grade</b>							
		24	Rigid-Horiz-25-Polystryrene- 2.00"	1,708.00 sf	939	2,172	-		1.82 /sf	3,112
			<b>Insulation - Building - Rigid - Slab On Grade</b>		<b>939</b>	<b>2,172</b>			/SF	<b>3,112</b>
			<b>INSULATION</b>		<b>2,025</b>	<b>3,578</b>			/SF	<b>5,602</b>
<b>7500.00</b>			<b>ROOFING</b>							
	<b>7510.00</b>		<b>Roofing - General</b>							
		10	Roofing-Existing-Remains	0.00 ls	-	-	0		0.00 /ls	0
	<b>7528.00</b>		<b>Roofing - Membrane</b>							
		24	Roofing-Memb-W/Rigid	1,000.00 sf	-	-	12,500		12.50 /sf	12,500
		26	Roofing-Memb-W/Rigid-SF-Avg 2	1,897.00 sf	-	-	28,455		15.00 /sf	28,455
		122	Roofing-Memb-SF-Flashings-Facia- 6"	70.00 lf	-	-	1,050		15.00 /lf	1,050
			<b>Roofing - Membrane</b>				<b>42,005</b>		/SF	<b>42,005</b>
	<b>7810.00</b>		<b>Roofing - Roof Hatches</b>							
		20	Roof Hatch-36" x 36"-Alum	1.00 ea	480	1,400	-		1,880.00 /ea	1,880
			<b>Roofing - Roof Hatches</b>		<b>480</b>	<b>1,400</b>			/SF	<b>1,880</b>
			<b>ROOFING</b>		<b>480</b>	<b>1,400</b>	<b>42,005</b>			<b>43,885</b>
<b>7900.00</b>			<b>SEALANTS &amp; CAULKING</b>							
	<b>7920.00</b>		<b>Sealants &amp; Caulking</b>							
		32	Sealants-Exterior-Backer Rod-0.50"	1,016.00 lf	1,524	50	-		1.55 /lf	1,574
		42	Sealants-Exterior-Joint- 0.50" x 0.50"	1,016.00 lf	2,345	425	-		2.73 /lf	2,769
		100	Sealants-Boom Lift-To 40' H	80.00 hr	800	-			26.00 /hr	2,080
			<b>Sealants &amp; Caulking</b>		<b>3,869</b>	<b>1,275</b>			/SF	<b>6,424</b>
			<b>SEALANTS &amp; CAULKING</b>		<b>3,869</b>	<b>1,275</b>			/SF	<b>6,424</b>
<b>8000.00</b>			<b>DOORS &amp; FRAMES</b>							
	<b>8110.00</b>		<b>Hollow Metal - Doors</b>							
		20	Hollow Metal-Door-20 Ga-To 4070-Flush	18.00 ea	1,080	4,230	-		295.00 /ea	5,310
		24	Hollow Metal-Door-16 Ga-To 4070-Flush	10.00 ea	600	2,950	-		355.00 /ea	3,550
		30	Hollow Metal-Door-Add-Galv	3.00 ea	-	150	-		50.00 /ea	150
		32	Hollow Metal-Door-Add-Insulated	3.00 ea	-	150	-		50.00 /ea	150
		36	Hollow Metal-Door-Add-Lite-HG	5.00 ea	-	750	-		150.00 /ea	750
		40	Hollow Metal-Door-Add-Stiffened	8.00 ea	-	2,400	-		300.00 /ea	2,400
		70	Hollow Metal-Door-Unload & Stock	28.00 ea	315	-	-		11.25 /ea	315
			<b>Hollow Metal - Doors</b>		<b>1,995</b>	<b>10,630</b>			/SF	<b>12,625</b>
	<b>8120.00</b>		<b>Hollow Metal - Frames</b>							
		20	Hollow Metal-Frame-16 Ga-To 4070-Std	50.00 ea	3,000	6,250	-		185.00 /ea	9,250
		30	Hollow Metal-Frame-Add-14 Ga	8.00 ea	-	360	-		45.00 /ea	360
		36	Hollow Metal-Frame-Add-Galv	3.00 ea	-	90	-		30.00 /ea	90
		40	Hollow Metal-Frame-Add-Light-Sides	0.00 sf	0	0	-		0.00 /sf	0
		52	Hollow Metal-Frame-Cased Opng- 4' x 4'	2.00 ea	180	500	-		340.00 /ea	680
		60	Hollow Metal-Frame-Unload & Stock	51.00 ea	383	-	-		7.50 /ea	383
			<b>Hollow Metal - Frames</b>		<b>3,563</b>	<b>7,200</b>			/SF	<b>10,763</b>
	<b>8210.00</b>		<b>Wood Doors</b>							
		30	Wood Doors-SC-To 4070-Maple-Flush	21.00 ea	1,890	9,975	-		565.00 /ea	11,865
		52	Wood Doors-SC-Add-Lite-Half Glass	10.00 ea	-	1,500	-		150.00 /ea	1,500
		64	Wood Doors-SC-Add-Prefinished	21.00 ea	-	630	-		30.00 /ea	630
		68	Wood Doors-SC-Add-UL Rating	0.00 ea	-	0	-		0.00 /ea	0
		72	Wood Doors-SC-Unload & Stock	21.00 ea	236	-	-		11.25 /ea	236
			<b>Wood Doors</b>		<b>2,126</b>	<b>12,105</b>			/SF	<b>14,231</b>
	<b>8214.00</b>		<b>Wood Doors - Custom</b>							
		14	Wood Doors-Custom-Exist-Repairs	2.00 ea	650	1,000	-		825.00 /ea	1,650
			<b>Wood Doors - Custom</b>		<b>650</b>	<b>1,000</b>			/SF	<b>1,650</b>
			<b>DOORS &amp; FRAMES</b>		<b>8,334</b>	<b>30,935</b>				<b>39,269</b>
<b>8300.00</b>			<b>SPECIAL DOORS</b>							
	<b>8330.00</b>		<b>Cooling Doors</b>							
		70	Cooling Door-Counter-Steel- 4' x 4'	2.00 ea	-	-	4,000		2,000.00 /ea	4,000
			<b>Cooling Doors</b>				<b>4,000</b>		/SF	<b>4,000</b>
	<b>8332.00</b>		<b>Overhead Doors</b>							
		20	Overhead Door-Steel-Sectional- 8' x 8'	1.00 ea	-	-	1,600		1,600.00 /ea	1,600
		30	Overhead Door-Add-Motor Operated	1.00 ea	-	-	1,650		1,650.00 /ea	1,650
			<b>Overhead Doors</b>				<b>3,250</b>		/SF	<b>3,250</b>
			<b>SPECIAL DOORS</b>				<b>7,250</b>			<b>7,250</b>
<b>8500.00</b>			<b>WINDOWS</b>							
	<b>8530.00</b>		<b>Windows - Wood</b>							
		20	Windows-Wood-Clad-New	120.00 sf	1,150	5,400	9,000	250	131.67 /sf	15,800
		22	Windows-Wood-Clad-Replacements	612.00 sf	5,865	612	45,900	1,275	87.67 /sf	53,652
			<b>Windows - Wood</b>		<b>7,015</b>	<b>6,012</b>	<b>54,900</b>	<b>1,525</b>	<b>/SF</b>	<b>69,452</b>
<b>8700.00</b>			<b>DOOR HARDWARE</b>							
	<b>8702.00</b>		Door Hardware - General							

**Standard Estimate Report**  
St Johnsbury - Police Station - Armory

February 14, 2021

Group	Phase	Item	Description	Takeoff Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Total Cost/Unit	Total Amount
	8702.00		<b>Door Hardware - General</b>							
		26	Door Hardware-Per Set-Secure	8.00 ea	2,400	5,600	-	-	1,000.00 /ea	8,000
		28	Door Hardware-Per Set-Commons	41.00 ea	7,380	13,325	-	-	505.00 /ea	20,705
			<b>Door Hardware - General</b>		<b>9,780</b>	<b>18,925</b>	<b>18,925</b>		<b>/SF</b>	<b>28,705</b>
	8800.00		<b>GLASS &amp; GLAZING</b>							
	8810.00		<b>Glass &amp; Glazing</b>							
		66	Glass & Glazing-Temper- 1/4"	180.00 sf	-	-	4,500	-	25.00 /sf	4,500
			<b>Glass &amp; Glazing</b>				<b>4,500</b>		<b>/SF</b>	<b>4,500</b>
			<b>GLASS &amp; GLAZING</b>				<b>4,500</b>		<b>/SF</b>	<b>4,500</b>
	9250.00		<b>GYPSUM WALLBOARD</b>							
	9252.00		<b>Gypsum Wallboard - General</b>							
		62	Gypsum-Field Foreman	5.00 wk	14,000	-	-	-	2,800.00 /wk	14,000
		92	Gypsum-Matri Handling-Unload & Stock-By Hr	26.00 hr	1,560	-	-	1,625	122.50 /hr	3,185
		146	Ceilings-SF-358MS/18ga/158X/Tape	213.00 sf	1,042	337	-	40	6.67 /sf	1,420
			<b>Gypsum Wallboard - General</b>		<b>16,602</b>	<b>337</b>	<b>337</b>	<b>1,665</b>	<b>/SF</b>	<b>18,605</b>
	9254.00		<b>Metal Framing - Load Bearing</b>							
		30	LGMF-Track-Std- 600 x 16 Ga	304.00 lf	-	585	-	-	1.93 /lf	585
		66	LGMF-Track-Deep- 600 x 16 Ga	152.00 lf	-	326	-	-	2.15 /lf	326
		110	LGMF-Stud-CSJ- 600 x 16 Ga	2,366.00 lf	-	5,075	-	-	2.15 /lf	5,075
		190	LGMF-CR Bridging-Clip Angles	232.00 ea	503	140	-	-	2.77 /ea	643
		192	LGMF-CR Bridging-Clip Channel-16 Ga	304.00 lf	304	150	-	-	1.50 /lf	454
		*202	LGMF-Fastener-Shots & Pins	1,779.00 ea	-	881	-	-	0.50 /ea	881
		204	LGMF-Sill Seal-Standard	152.00 lf	99	18	-	-	0.77 /lf	117
		260	LGMF-Labor-Wall- 600 x 16 Ga x 16" o.c.	1,976.00 sf	6,257	-	-	-	3.17 /sf	6,257
			<b>Metal Framing - Load Bearing</b>		<b>7,163</b>	<b>7,176</b>	<b>7,176</b>		<b>/SF</b>	<b>14,339</b>
	9256.00		<b>Metal Framing - Non Load Bearing</b>							
		38	LGMF-Track- 358 x 20 Ga	2,068.00 lf	-	1,365	-	-	0.66 /lf	1,365
		60	LGMF-Track-Deep- 358 x 18 Ga	1,034.00 lf	-	2,730	-	-	2.64 /lf	2,730
		88	LGMF-Stud- 358 x 20 Ga	12,619.50 sf	-	6,663	-	-	0.53 /lf	6,663
		180	LGMF-Labor-Wall- 358 x 16" o.c.	11,994.00 sf	31,651	-	-	-	2.64 /sf	31,651
			<b>Metal Framing - Non Load Bearing</b>		<b>31,651</b>	<b>10,758</b>	<b>10,758</b>		<b>/SF</b>	<b>42,409</b>
	9258.00		<b>Ceiling Suspension Systems</b>							
		20	GWBC-Suspension Grid-650 Type	451.00 sf	-	-	902	-	2.00 /sf	902
			<b>Ceiling Suspension Systems</b>				<b>902</b>		<b>/SF</b>	<b>902</b>
	9260.00		<b>Gypsum Wallboard</b>							
		*30	GWB-Hung-Firecode-5/8"-Type X	26,415.00 sf	28,679	12,204	-	-	1.55 /sf	40,883
		68	GWB-Hung-Sheathing-5/8"-DensGlass	1,976.00 sf	2,145	1,484	-	-	1.84 /sf	3,630
		*80	GWB-Hung-Add-Above 10' H	3,764.00 sf	1,748	-	-	-	0.46 /sf	1,748
		112	GWB-Caulk-Acoustic- 0.50" x 0.50"	2,068.00 lf	5,170	1,137	-	-	3.05 /lf	6,307
		*144	GWB-Finish Tape-Fire-1 Coat	4,592.00 sf	1,327	505	-	-	0.40 /sf	1,832
		*146	GWB-Finish Tape-3 Coat	21,823.00 sf	11,348	3,961	-	-	0.70 /sf	15,309
			<b>Gypsum Wallboard</b>		<b>50,417</b>	<b>19,291</b>	<b>19,291</b>		<b>/SF</b>	<b>69,708</b>
	9299.00		<b>Gypsum Wallboard - Misc</b>							
		64	GWB-Insul-Wall-MF- 6.00"-UF-R11	1,976.00 sf	948	2,934	-	-	1.97 /sf	3,883
		68	GWB-Insul-Wall-FG- 3.50"-KF-R11	11,994.00 sf	5,757	4,618	-	-	0.87 /sf	10,375
			<b>Gypsum Wallboard - Misc</b>		<b>6,706</b>	<b>7,552</b>	<b>7,552</b>		<b>/SF</b>	<b>14,258</b>
			<b>GYPSUM WALLBOARD</b>		<b>112,538</b>	<b>45,115</b>	<b>45,115</b>	<b>902</b>	<b>1,665</b>	<b>160,220</b>
	9300.00		<b>TERRAZZO &amp; TILE</b>							
	9312.00		<b>Ceramic Tile</b>							
		44	Ceramic Tile-Wall-Glazed- 4" x 4"	2,248.00 sf	-	-	17,984	-	8.00 /sf	17,984
		72	Ceramic Tile-Floor-Porcelain- 2" x 2"	920.00 sf	-	-	7,820	-	8.50 /sf	7,820
		90	Ceramic Tile-Add-Mudset	216.00 sf	-	-	864	-	4.00 /sf	864
		92	Ceramic Tile-Add-Membrane-Waterproof	200.00 sf	-	-	800	-	4.00 /sf	800
			<b>Ceramic Tile</b>				<b>27,468</b>		<b>/SF</b>	<b>27,468</b>
			<b>TERRAZZO &amp; TILE</b>				<b>27,468</b>		<b>/SF</b>	<b>27,468</b>
	9500.00		<b>ACOUSTICAL TREATMENT</b>							
	9510.00		<b>Acoustical Ceilings</b>							
		42	ACT Ceilings-SF-Fissured-2 x 2	9,990.00 sf	-	-	39,960	-	4.00 /sf	39,960
			<b>Acoustical Ceilings</b>				<b>39,960</b>		<b>/SF</b>	<b>39,960</b>
			<b>ACOUSTICAL TREATMENT</b>				<b>39,960</b>		<b>/SF</b>	<b>39,960</b>
	9600.00		<b>CARPET &amp; RESILIENT</b>							
	9610.00		<b>Carpet &amp; Resilient - General</b>							
		14	Carpet & Resilient-Flooring	9,611.00 sf	-	-	43,250	-	4.50 /sf	43,250
			<b>Carpet &amp; Resilient - General</b>				<b>43,250</b>		<b>/SF</b>	<b>43,250</b>
			<b>CARPET &amp; RESILIENT</b>				<b>43,250</b>		<b>/SF</b>	<b>43,250</b>
	9700.00		<b>SPECIAL FLOORING</b>							
	9710.00		<b>Special Flooring - General</b>							
		34	Floor-Concrete-Sealer	966.00 sf	-	-	1,449	-	1.50 /sf	1,449
			<b>Special Flooring - General</b>				<b>1,449</b>		<b>/SF</b>	<b>1,449</b>
	9720.00		<b>Special Flooring - Epoxy</b>							
		20	Floor-Epoxy-Quartz Chip-3/8"	592.00 sf	-	-	4,736	-	8.00 /sf	4,736
			<b>Special Flooring - Epoxy</b>				<b>4,736</b>		<b>/SF</b>	<b>4,736</b>

**Standard Estimate Report**  
*St Johnsbury - Police Station - Armory*

February 14, 2021

Group	Phase	Item	Description	Takeoff Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Total Cost/Unit	Total Amount
			<b>SPECIAL FLOORING</b>				<b>6,185</b>		/SF	<b>6,185</b>
<b>9900.00</b>			<b>FINISH PAINT</b>							
	<b>9910.00</b>		Finish Paint - Exterior							
		10	Exterior Paint-Exist-No Work	0.00 ls	-	-	0	0.00 /ls		0
	<b>9920.00</b>		Finish Paint - Interior							
		14	Interior Paint-Finish	11,169.00 sf	-	-	33,507	3.00 /sf	33,507	
			Finish Paint - Interior				<b>33,507</b>	/SF	<b>33,507</b>	
			<b>FINISH PAINT</b>				<b>33,507</b>	/SF	<b>33,507</b>	
<b>10000.00</b>			<b>SPECIALTIES</b>							
	<b>10100.00</b>		<b>Chalkboards &amp; Tackboards</b>							
		10	Boards-Visual Display-Allowance	1.00 ls	-	-	5,000	5,000.00 /ls	5,000	
			Chalkboards & Tackboards				<b>5,000</b>	/SF	<b>5,000</b>	
	<b>10270.00</b>		<b>Access Flooring</b>							
		10	Access Floor-Raised-Computer Type	0.00 sf	-	-	0	0.00 /sf		0
	<b>10400.00</b>		<b>Identifying Devices</b>							
		16	Signage-Exterior-By Owner	0.00 ls	-	-	0	0.00 /ls		0
		52	Signage-Interior-Plaque-Plastic-To 8" x 8"	47.00 ea	2,115	3,525	-	120.00 /ea	5,640	
			Identifying Devices		<b>2,115</b>	<b>3,525</b>		/SF	<b>5,640</b>	
	<b>10500.00</b>		<b>Lockers</b>							
		40	Lockers-Team-Metal-Tier-Single	27.00 ea	1,620	9,450	-	410.00 /ea	11,070	
			Lockers		<b>1,620</b>	<b>9,450</b>		/SF	<b>11,070</b>	
	<b>10800.00</b>		<b>Toilet &amp; Bath Accessories</b>							
		36	TA-Wall Unit-PTD & WR-SM-B3699	8.00 ea	720	1,880	-	325.00 /ea	2,600	
		66	TA-Grab Bar-SS- 1.50" x 36"	8.00 ea	288	272	-	70.00 /ea	560	
		68	TA-Grab Bar-SS- 1.50" x 42"	8.00 ea	384	288	-	84.00 /ea	672	
		120	TA-Mirror-B165-24" x 36"	8.00 ea	360	760	-	140.00 /ea	1,120	
		152	TA-Mop Strip-B223 x 36"	8.00 ea	360	736	-	137.00 /ea	1,096	
		194	TA-Robe Hook-B2116	8.00 ea	120	144	-	33.00 /ea	264	
		216	TA-Soap Dispenser-SM-B2112	8.00 ea	240	328	-	71.00 /ea	568	
		266	TA-TPH-SM-B273-Dble	8.00 ea	240	168	-	51.00 /ea	408	
			Toilet & Bath Accessories		<b>2,712</b>	<b>4,576</b>		/SF	<b>7,288</b>	
			<b>SPECIALTIES</b>		<b>6,447</b>	<b>17,551</b>	<b>5,000</b>	/SF	<b>28,998</b>	
<b>11000.00</b>			<b>EQUIPMENT</b>							
	<b>11130.00</b>		<b>Audio Visual Equipment</b>							
		14	AV Equipment-Projection-Allowance	1.00 ls	-	-	2,000	2,000.00 /ls	2,000	
			Audio Visual Equipment				<b>2,000</b>	/SF	<b>2,000</b>	
	<b>11140.00</b>		<b>Service Station Equipment</b>							
		10	Service Equip-Vehicle-By Owner	0.00 ls	-	-	0	0.00 /ls		0
	<b>11450.00</b>		<b>Residential Equipment</b>							
		26	RA-Range-Elec	1.00 ea	55	650	-	705.00 /ea	705	
		66	RA-Micro Hood	1.00 ea	110	450	-	560.00 /ea	560	
		82	RA-Refrigerator-Top Mount	1.00 ea	55	800	-	855.00 /ea	855	
		90	RA-Dishwasher	1.00 ea	55	600	-	655.00 /ea	655	
		122	RA-Disposal	1.00 ea	83	150	-	232.50 /ea	233	
			Residential Equipment		<b>358</b>	<b>2,650</b>		/SF	<b>3,008</b>	
	<b>11800.00</b>		<b>Detention Equipment</b>							
		28	Detention Equip-Bunk-SS-Single	2.00 ea	-	-	3,400	1,700.00 /ea	3,400	
		40	Detention Equip-Bench	2.00 ea	-	-	3,000	1,500.00 /ea	3,000	
			Detention Equipment		<b>358</b>	<b>6,400</b>		/SF	<b>6,400</b>	
			<b>EQUIPMENT</b>		<b>2,650</b>	<b>8,400</b>		/SF	<b>11,408</b>	
<b>12000.00</b>			<b>FURNISHINGS</b>							
	<b>12010.00</b>		<b>Furnishings - General</b>							
		10	Furnishings-Loose-By Owner	0.00 ls	-	-	0	0.00 /ls		0
		14	Furnishings-Dispatch-By Owner	0.00 ls	-	-	0	0.00 /ls		0
		16	Furnishings-Office-By Owner	0.00 ls	-	-	0	0.00 /ls		0
<b>14000.00</b>			<b>CONVEYING SYSTEMS</b>							
	<b>14200.00</b>		<b>Elevators - Hydraulic</b>							
		14	Elevator-Hydraulic-3500 LB-Holeless	3.00 st	-	-	105,600	35,200.00 /st	105,600	
			Elevators - Hydraulic				<b>105,600</b>	/SF	<b>105,600</b>	
			<b>CONVEYING SYSTEMS</b>				<b>105,600</b>	/SF	<b>105,600</b>	
<b>15100.00</b>			<b>FIRE PROTECTION</b>							
	<b>15110.00</b>		<b>Fire Protection - Sprinkler</b>							
		12	Sprinkler-System-Wet	12,214.00 sf	-	-	36,642	3.00 /sf	36,642	
		14	Sprinkler-System-Dry	1,000.00 sf	-	-	6,000	6.00 /sf	6,000	
		16	Sprinkler-Storage Tanks	0.00 ea	-	-	0	0.00 /ea	0	
		18	Sprinkler-Fire Pump	0.00 ea	-	-	0	0.00 /ea	0	
			Fire Protection - Sprinkler				<b>42,642</b>	/SF	<b>42,642</b>	
			<b>FIRE PROTECTION</b>				<b>42,642</b>	/SF	<b>42,642</b>	
<b>15400.00</b>			<b>PLUMBING</b>							
	<b>15410.00</b>		<b>Plumbing - Estimates</b>							
		10	Plumbing-New-Fixtures	26.00 ls	-	-	104,000	4,000.00 /ls	104,000	
		12	Plumbing-New-Detention Fixtures	2.00 ea	-	-	13,000	6,500.00 /ea	13,000	
		22	Plumbing-Roof Drains	4.00 ea	-	-	12,000	3,000.00 /ea	12,000	
			Plumbing - Estimates				<b>129,000</b>	/SF	<b>129,000</b>	
			<b>PLUMBING</b>				<b>129,000</b>	/SF	<b>129,000</b>	
<b>15500.00</b>			<b>HVAC SYSTEMS</b>							

Group	Phase	Item	Description	Takeoff Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Total Cost/Unit	Total Amount
			<b>HVAC - Estimates</b>							
		12	HVAC-Heat & Cool-Rooftops-Gas-Ducted	12,214.00 sf	-	-	305,350	-	25.00 /sf	305,350
			<b>HVAC - Estimates</b>				<b>305,350</b>		<b>/SF</b>	<b>305,350</b>
			<b>HVAC SYSTEMS</b>				<b>305,350</b>		<b>/SF</b>	<b>305,350</b>
<b>16100.00</b>			<b>ELECTRICAL SYSTEMS</b>							
			<b>Electrical - Estimates</b>							
		10	Electrical-Building-Data/FA/Light/Mech/Power	12,214.00 sf	-	-	268,708	-	22.00 /sf	268,708
			20 Electrical-Light/Power-Carport	1,000.00 sf	-	-	7,500	-	7.50 /sf	7,500
			28 Electrical-Site-Lighting	0.00 ea	-	-	0	-	0.00 /ea	0
			30 Electrical-Site-Power-Primary	0.00 ls	-	-	0	-	0.00 /ls	0
			34 Electrical-Power Company Charges	0.00 ls	-	-	0	-	0.00 /ls	0
			60 Electrical-Generator-Emergency	1.00 ls	-	-	45,000	-	45,000.00 /ls	45,000
			<b>Electrical - Estimates</b>				<b>321,208</b>		<b>/SF</b>	<b>321,208</b>
			<b>ELECTRICAL SYSTEMS</b>				<b>321,208</b>		<b>/SF</b>	<b>321,208</b>
<b>20100.00</b>			<b>ALLOWANCES</b>							
			<b>Allowances</b>							
		10	Allowance-Masonry-Exterior-Restoration	4,070.00 sf	-	-	81,400	-	20.00 /sf	81,400
			<b>Allowances</b>				<b>81,400</b>		<b>/SF</b>	<b>81,400</b>
			<b>ALLOWANCES</b>				<b>81,400</b>		<b>/SF</b>	<b>81,400</b>
<b>20700.00</b>			<b>SPECIAL PROJECT REQUIREMENTS</b>							
			<b>Green Construction</b>							
		10	Green Construction-Not Included	0.00 ls	-	-	0	-	0.00 /ls	0

**Estimate Totals**

Description	Amount	Totals	Hours	Rate	Cost Basis	Cost per Unit	Percent of Total
Vermont State & City Sales Tax	<b>2,628,561</b>	<b>2,628,561</b>					
Escalation-1 Year	197,142			7.500 %			
General Requirements	84,771			3.000 %			
General Conditions	203,733			7.000 %			
Estimate Contingency	311,421			10.000 %			
	<b>797,067</b>	<b>3,425,628</b>					
Insurances	27,143			0.750 %			
P & P Bond	27,143			0.750 %			
	<b>54,286</b>	<b>3,479,914</b>					
OHD & Profit-Hard Bid	139,197			4.000 %			
	<b>139,197</b>	<b>3,619,111</b>					
<b>Total</b>		<b>3,619,111</b>					